



221520010916

No. 051399-2023

检验报告

TEST REPORT

样品名称：自粘聚合物改性沥青防水卷材

型号规格：自粘卷材 PY I PE 3.0 10

送检单位：东营正宇防水材料有限公司

检验类别：委托抽样（型式检验）

山东省乡镇企业建材质量监督检验中心

Shandong Township Enterprise Building Materials Quality Supervision and Inspection Center



山东省乡镇企业建材质量监督检验中心

Shandong Township Enterprise Building Materials Quality Supervision and Inspection Center


检验报告

Test Report


共 3 页第 1 页

产品名称 Product	自粘聚合物改性沥青防水卷材	检验类别 Test Kind	委托抽样 (型式检验)
受检单位 Supervised Enterprise	东营正宇防水材料有限公司	型号规格 Model, Type	自粘卷材 PY I PE 3.0 10
生产单位 Manufacturer	东营正宇防水材料有限公司	样品等级 Grade	/
受检单位地址 Address of Supervised Enterprise	广饶县稻庄镇庞项村	商 标 Brand	正顺
抽样地点 Sampling Location	企业成品库	抽样人员 Sampling Personnel	张光明、张饮饮
抽样基数 Sample Batch	2000m ²	抽样日期 Sampling Date	2023-04-13
样品数量 Sample Quantity	全幅 2.0m/5 卷	接样日期 Receipt Date	2023-04-13
样品特性和状态 Sample Description	卷状, 正常	生产日期 Producing Date	2023-04-03
样品批号 Batch No.	/	检验日期 Test Date	2023-04-14~2023-05-04
检验依据 Test Standard	GB 23441-2009		
检验要求 Test Item	型式检验		
检验结论 Test Conclusion	该批产品按 GB 23441-2009 标准检验合格。 		
备 注 Note	1、本报告含封面及封三, “/” 符号表示空项。 2、单位面积质量、面积、厚度、外观现场检验。		


批准:


 日期: 2023-05-04

审核:


 日期: 2023-05-04

编制:


 日期: 2023-05-04

山东省乡镇企业建材质量监督检验中心

检验报告 (续页)

共 3 页第 2 页

序号	检验项目		单位	技术要求	检验结果	单项判定	
1	面积, %		/	≥ 99	100.7, 100.6, 100.7, 100.7, 100.8	合格	
2	单位面积质量		kg/m ²	≥ 3.1	3.2, 3.2, 3.3, 3.4, 3.3	合格	
3	厚度	平均值	mm	≥ 3.0	3.14, 3.16, 3.14, 3.14, 3.15	合格	
		最小值		≥ 2.7	3.09, 3.13, 3.08, 3.10, 3.11		
4	外观质量	端面里进外出	mm	不得超过 20	6, 7, 4, 6, 6	合格	
		裂纹或粘结	/	在距卷芯 1000mm 长度外不应有裂纹或长度 10mm 以上的粘结	符合要求		
		胎基	/	胎基应浸透, 不应有未被浸渍的浅色条纹	符合要求		
		卷材表面	/	表面平整, 不允许有孔洞、结块、气泡、缺边和裂口, 上表面为细砂的, 细砂应均匀一致并紧密地粘附于卷材表面	符合要求		
		接头	/	每卷卷材接头不应超过一个, 较短的一段长度不应少于 1000mm, 接头应剪切整齐, 并加长 150mm	符合要求		
5	可溶物含量		g/m ²	≥ 2100	2197	合格	
6	拉伸性能	拉力	纵向	N/50mm	≥ 450	1060	合格
			横向		≥ 450	1015	
		最大拉力时延伸率, %	纵向	/	≥ 30	52	合格
			横向		≥ 30	56	
7	耐热性		/	70℃ 无滑动、流淌、滴落	3 片均无滑动、流淌、滴落	合格	
8	低温柔性		/	-20℃ 无裂纹	下表面 5 片均无裂纹 上表面 5 片均无裂纹	合格	
9	不透水性		/	0.3MPa, 120min 不透水	3 片均不透水	合格	

山东省乡镇企业建材质量监督检验中心

检 验 报 告 (续页)

共 3 页第 3 页

序号	检验项目		单位	技术要求	检验结果	单项判定		
10	剥离强度	卷材与卷材	N/mm	≥ 1.0	1.3	合格		
		卷材与铝板		≥ 1.5	1.7			
11	钉杆水密性		/	通过	通过	合格		
12	渗油性, 张数		/	≤ 2	1	合格		
13	持粘性		min	≥ 15	43	合格		
14	热老化	最大拉力时延伸率, %	纵向	/	≥ 30	48	合格	
			横向	/	≥ 30	54		
		低温柔性		/	-18℃ 无裂纹	下表面 5 片均无裂纹 上表面 5 片均无裂纹		
		剥离强度	卷材与铝板	N/mm	≥ 1.5	1.7		
		尺寸稳定性, %		/	≤ 1.5	0.3		
15	自粘沥青再剥离强度		N/mm	≥ 1.5	1.7	合格		
备 注			/					

*****以下空白*****

声 明

- 1、报告无“检验报告专用章”无效。
- 2、复制报告未重新加盖“检验报告专用章”无效。
- 3、报告无审核、批准人签字无效。
- 4、报告涂改无效。
- 5、除全文复制外,未经本机构批准不得部分复制报告。
- 6、送样检验,检验结果仅对来样负责。
- 7、送样检验样品及相关信息,均由委托单位提供,本机构不对其真实性及完整性负责。
- 8、如对本报告有异议,请于收到报告之日起15日内提出,逾期不予受理。



STATEMENT

- 1、The report without the specific seal for inspection report is invalid.
- 2、The copy of report without the specific seal for inspection report is invalid.
- 3、The report will be invalid without signature of person who was authorized to verify or approve it.
- 4、The report is not valid if altered.
- 5、This report can only be reproduced in whole and may not be partially reproduced without approval of this agency.
- 6、The report of sample-delivery test is valid only for the samples delivered by the clients.
- 7、Samples sent for inspection and related information are provided by the entrusting organization, and this agency is not responsible for its authenticity and integrity.
- 8、If there is any objection concerning the report, please submit it within 15 days upon reception of the report. The overdue request will not be accepted.

地址: 山东省泰安市迎春路35号

邮编: 271000

电话: (0538) 8222026

传真: (0538) 8226159